



## Addition of 1,4-dioxane removal system to municipal water treatment plant: pilot to operation

Ali Ling, PhD, PE

### **Acknowledgements:**


Katie Wolohan, PE

Julie Macejkovic, PE

Abby Morrisette, PE


Andy McCabe, PhD

# City of New Brighton, Minnesota groundwater contamination




A single treatment system that solves two problems associated with TCAAP groundwater contamination.


# New Brighton groundwater sources



# Contaminated groundwater treatment history



# 1,4-Dioxane



**1,4-dioxane molecule**

	1,4-Dioxane Concentration
Federal SDWA	No limit
Michigan Drinking Water Criterion	7.2 µg/L
Minnesota Health Risk Limit (since 2013)	1.0 µg/L
New Brighton WTP1 wells	1.0-6.8 µg/L

# Pilot planning: 1,4-Dioxane treatment technology evaluation



Research potential technologies



Select technology for pilot test

## **2 advanced oxidation processes (AOPs)**

- Demonstrated application at scale
- Removal of 1,4-DX to target levels
- Scalable pilot potential



# Pilot planning: test equipment




APT HiPOx Pilot System




Trojan UVPhox Pilot System  
(low pressure UV lamps)

# Pilot planning: chemical treatment of 1,4-Dioxane by advanced oxidation

## UV-Peroxide





## Ozone-Peroxide






# Pilot planning: existing WTP1 processes





# Pilot planning: WTP1 process with AOP addition

Designed 50 gpm pilot to simulate existing WTP1 treatment processes with AOP.



# Pilot Planning: 1,4-Dioxane treatment technology evaluation



Research potential technologies



Develop screening criteria



Select technologies for pilot test



Perform treatability testing

## Two advanced oxidation processes (AOPs)


- Demonstrated application at scale
- Removal of 1,4-DX to target levels
- Scalable pilot potential

# Pilot planning: risk assessment






# Pilot planning: risks and objectives




# Pilot planning: risks and objectives




# Pilot planning: testing phases and runs

Phase	Description	Duration (6 months total)
0	Pilot Start-Up and Training	1 month
1	AOP Optimization	3 months
2	Continuous Run	2 months
3	GAC Optimization	5 months (concurrent <i>with Phases 1 and 2</i> )
4	Hydroxyl Scavenger Testing	Short; conducted when convenient

# Results: operational settings – UV AOP




# Results: operational settings – Ozone AOP







# Results: 1,4-DX removal consistency



# Results: VOC removal by AOPs




- 1,1,1-Trichloroethane
- 1,1-Dichloroethane
- 1,1-Dichloroethylene
- 1,2-Dichloroethylene



- 1,1,1-Trichloroethane
- 1,1-Dichloroethane
- VOCs Removed by Ozone AOP

# Results: sensitivity to GSF performance



# Results: effect of AOP on downstream GAC



Currently-used  
Calgon F400 GAC  
effective for  
quenching peroxide -  
no special catalytic  
carbon required

## Results: byproducts and distribution system

- VOC and SVOC tentatively identified compounds (TICs) scanned to measure byproducts
- Simulated distribution system bench tests to evaluate effect on disinfection by-product formation
- Assimilable organic carbon (AOC) through treatment steps analyzed to evaluate effect on microbial regrowth



## Results: byproducts and distribution system

- VOC and SVOC tentatively identified compounds (TICs) scanned to measure byproducts


**No significant  
changes**

- Simulated distribution system bench tests to evaluate effect on disinfection by-product formation

**anticipated**

- Assimilable organic carbon (AOC) through treatment steps analyzed to evaluate effect on microbial regrowth



# Results: hydroxyl scavenging




## Results: pilot summary

	UV AOP	Ozone AOP
Meets 1,4-Dioxane target (1/10 <sup>th</sup> of current MDH HRL)	Yes	Yes
Removes most VOCs	Yes	Yes
Peroxide dose	8 mg/L	23 mg/L
Peroxide residual	4 mg/L	16 mg/L
Byproducts	None identified	Bromate, with high health risk

# Results: AOP cost comparison




# Design: interim water supply measures






# Design: WTP1 prior to July 2016



# Design: Minneapolis interconnection and WTP1 upgrade





# Design: Minneapolis interconnection


- Switch from groundwater to surface water
- Barr supported corrosion control planning and monitoring



# Design: distribution control station




# Design: WTP1 upgrade through startup






# Where we're headed: the long-term solution.



# New Layout

Addition of Trojan UVPhox™ equipment will require expansion of existing WTP1.




## Design: operating conditions

- **7.3 MGD** (design flow)
- **5.1 MGD** (typical annual peak day)
- **96% UVT** (typical based on pilot study)
- **3 trains** available
- **2.0-log removal** (Trojan guaranteed performance)



# Design: Trojan UV-AOP equipment

Three treatment trains are installed in parallel, each with two treatment units.



# Design: WTP1 expansion additional improvements

Site landscaping has been revised to implement sustainable water use and storm water management practices.



# Additional Improvements




- System-wide upgrade of SCADA and controls
- Expanded electrical equipment and generator capacity
- Piping changes to accommodate flow reconfiguration
- Valve upgrades for existing processes
- HVAC and lighting upgrades
- Refinishing of portions of the existing exterior finishes

# Start-up Fall 2018




# Design: WTP1 upgrade through startup






# Full-scale Performance




# ADVANCED OXIDATION



Hydroxyl radical ( $\text{OH}^*$ ) is a short-lived, very strong oxidant  
Make it in AOPs using selected chemistry


# ADVANCED OXIDATION



Reason for using AOP is to remove 1,4-dioxane (DX)



# HYDROXYL RADICAL SCAVENGING



But other things react with (scavenge) hydroxyl radical


# AOP PROGRAMMING

ENTER IN

- Log-removal target
- Hydroxyl radical scavenging term


MEASUREMENTS

- Flow
- Inline UVT



DICTATES


- Peroxide pumping rate
- UV lamp power




CONTROLS

- Actual OH\* concentration
- 1,4-dioxane log-removal


# PROBLEM



# Hydroxyl Radical Scavenging Issue




# Hydroxyl Radical Scavenging Issue



# Hydroxyl Radical Scavenging Issue

- Removing hypochlorite as oxidant = no chloramines
- Need to be aware of breakpoint chlorination downstream



# Project Lessons Learned



- Scavenging term that best predicts removal may not match measured value
- Consider effect of process changes on downstream processes (e.g. moving breakpoint chlorination downstream)
- Make sure on-line monitoring equipment used to set treatment level (UVT) is functional



## Addition of 1,4-dioxane removal system to municipal water treatment plant: pilot to operation

Ali Ling, PhD, PE

### **Acknowledgements:**

Katie Wolohan, PE

Julie Macejkovic, PE

Abby Morrisette, PE

Andy McCabe, PhD